

## Geoelectric Monitoring of Bentonite Barrier Resaturation in the Äspö Prototype Repository

Final Report

Klaus Wieczorek  
Michael Komischke  
Rüdiger Miehe  
Helge Moog

Oktober 2014

### **Remark:**

This report was prepared under contract No. 02E9944 of the German Federal Ministry for Economic Affairs and Energy (BMWi). ✓

The work was conducted by the Gesellschaft für Anlagen- und Reaktorsicherheit (GRS) gGmbH.

The authors are responsible for the content of this report.

## Table of contents

<b>1</b>	<b>Introduction.....</b>	<b>1</b>
<b>2</b>	<b>Objectives .....</b>	<b>3</b>
<b>3</b>	<b>Fundamentals of geoelectrics .....</b>	<b>5</b>
3.1	Theory .....	5
3.2	Measuring technique .....	8
3.3	Evaluation method.....	9
<b>4</b>	<b>Preparatory work .....</b>	<b>11</b>
4.1	Laboratory calibration .....	11
4.1.1	Resistivity of MX-80 bentonite.....	11
4.1.2	Resistivity of the tunnel backfill .....	17
4.1.3	Resistivity of the rock.....	20
4.1.4	Change of solution composition by interaction with compacted MX-80 ....	21
4.2	Assessment of measurement resolution .....	33
4.2.1	Backfill.....	33
4.2.2	Buffer.....	36
<b>5</b>	<b>Instrumentation.....</b>	<b>39</b>
5.1	Measurement system .....	39
5.2	Electrode arrays and installation procedure .....	41
5.2.1	Backfill electrodes.....	42
5.2.2	Buffer electrodes.....	46
5.2.3	Rock electrodes.....	49
<b>6</b>	<b>In-situ measurements.....</b>	<b>51</b>
6.1	Backfill Section I .....	51
6.2	Backfill Section II .....	55
6.3	Buffer deposition hole #5 .....	57
6.4	Rock Section II .....	59

<b>7</b>	<b>Injection tests in the laboratory</b> .....	<b>65</b>
<b>8</b>	<b>Post-test investigations</b> .....	<b>67</b>
8.1	Electrode inspection .....	67
8.1.1	Backfill electrodes.....	67
8.1.2	Buffer electrodes.....	68
8.2	Buffer water content.....	70
<b>9</b>	<b>Conclusions</b> .....	<b>73</b>
	<b>Acknowledgements</b> .....	<b>75</b>
	<b>References</b> .....	<b>77</b>
	<b>List of figures</b> .....	<b>81</b>
	<b>List of tables</b> .....	<b>85</b>